

Schedule of works or proposals from parish

Installation of a new Audio Visual system within the Church.

- Remove existing Audio System.
- Remove existing Visual System.
- Installation of a new operators position in the rear nave with cabinet for equipment and a two person desk to operate equipment from.
- Installation of a new Audio System to cater for speech, recorded music and live music reproduction throughout the building. This will include an upgrade to the Chancel area where improvements will be made to make equipment more discrete in an area of significant spiritual importance.
- Installation of a new Video system
 - New double drop projector screen in front of the central nave archway with a front facing laser projector from the rear bell tower.
 - New screen fixed to the 'Vicar's Vestry' wooden panels that will serve the north aisle.
 - Two new screens fixed to the white Church pillars to serve the south aisle.
 - One new screen to serve the Choir Stalls position.
This position replaces an existing fitting.
 - Installation of two motorised PTZ Cameras.
 - Installation of a Live Vision mixer housed in the new operators cabinet which will facilitate live streaming of services and events from within the Church.
- Installation of a new Audio Induction Loop System.

The contractor will be B+H Audio Services - <http://www.bhsound.co.uk/who-we-are/>

Further details and associated documentation can be found within the application dated May 2021.